

4-041490

7-22  
15-065-30052-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1965

NE NE NE /4 SEC. 07, 09 S, 23 W  
4950 feet from S section line  
330 feet from E section line

Operator license# 5363 Lease Harvey well # 1

Operator: Berexco, Inc. County Graham

Address: Box 723 Well total depth 3935 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 222 feet w/150 sx.

127.88

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 22 Month: July Year: 93

Plugging proposal received from: Bob Grant

Company: Beren Corporation Phone:

Were: 4 1/2" casing set @ 3935' w/150 sx. cement. Perf. @ 3750'-3754'.  
Dakota @ 1200' - Anhy. @ 2065'.  
Ordered 300 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:00P.M., Day: 22, Month: July, Year: 93

Actual plugging report:  
R.I.H. with tubing @ 3878' spot 50 sx. w/150# hulls.  
R.I.H. with tubing @ 2837' spot 50 sx. w/100# hulls.  
R.I.H. with tubing @ 1765' spot 60 sx. w/150# hulls to circulate at surface and squeezed 50 sx. cement. Max. 900# P.S.I. S.I.P. 500#. 8 5/8" S.P. Squeezed 50 sx. cement w/50# hulls. Max. 200#. S.I.P. 200#.

Remarks:  
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING. Elevation: 2383 GL

I did [ X ] [ did not ] observe the plugging.

INVOICED

DATE 8-24-93  
INV. NO. 38394

7-22 OCT 05 1993

*Dennis J. James*  
(agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1993  
8-20-93  
CONSERVATION DIVISION  
Wichita, Kansas

Form CP-2/3