

15-065-20763-00-00

R

6 030589

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA

C.N.W.N.W., SEC. 10, T. 9 S, R. 23 W

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name QUINT Well # 1

Operator: NADEL & GUSSMAN

County GRAHAM 125.29

Name & Address 3232 FIRST NATIONAL TOWER

Well Total Depth 3855 feet

TULSA, OKLAHOMA

Conductor Pipe: Size _____ feet

74103

Surface Casing: Size 8 5/8 feet 174'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CEMENT CO. License Number _____

Address PLAINVILLE KANSAS

Company to plug at: Hour: PM Day: 29 Month: 10 Year: 19 85

Plugging proposal received from FRANK NEFF

(company name) NADEL & GUSSMAN (phone) _____

were: 8 5/8 SET @ 174' w/ 166 SX. 4 1/2 SET @ 3855' w/ 100 SX. Top PERF. 3762

RECOVERED 800' CASING. ORDER SAND & COM. CMT. FOR BOTTOM ORDER

200 SX. 60/40 POZ. 6% GEL 10 SX. GEL 4 SX. HULLS ALLIED CMT. CO.

WELLBROCK WATER TRUCKS

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5: PM Day: 29 Month: 10 Year: 19 85

ACTUAL PLUGGING REPORT Bottom Plug = 4 SX. CEMENT SAND TO 3680' 4 SX. CEMENT.

Top Plug. Pump Down 8 5/8 4 SX. HULLS 200 SX. CMT. MIX. MAX. PSI

900 PSI CLOSE IN 400 PSI PLUG COMPLETE

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

NOV 22 1985

DATE

INV. NO. 11142

STATE CORPORATIONS DIVISION

NOV 8 1985

CONSERVATION DIVISION

Carl Goodrow (TECHNICIAN)

11-8-85

FORM CP-2/3 Rev. 01-84

40 11-7-85 mgd