

To: **6 070908**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-11 183 R  
API NUMBER 15- 065-22,624 - 00-00  
C NW     , SEC. 10, T 9 S, R 23 WXX

3960 feet from S section line  
3960 feet from E section line

Lease Name Quint Well # 1  
County Graham 125.45

Well Total Depth 3860 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 208

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3007

Operator: Western Ks. Exploration  
Name & Address Bx 126  
Hays, Ks. 67601  
Stan Younger

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A X

Other well as hereinafter indicated     

Plugging Contractor Western Ks. Drilling License Number 4083  
Address Box 126 Hays, Ks. 67601

Company to plug at: Hour: AM Day: 11th Month: Mar Year: 19 91

Plugging proposal received from Dwight French

(company name) Western Ks. Drilling (phone)     

were: 8 5/8 - 208 ft. s.p. cwc w/135 sks 60/40 poz 2% gel 3% cc. by Halliburton.

L.K.G. Well. Elev. 2305 anyh 1947. No circ problems. Mud condition 9.8 lbs.

43 vis 12 w.l. Proposal 190 sks 60/40 poz 6% gel 3% cc. Spot and

displace cement w/drill stem, circ 42 -045 vis mud. Heavy mud between all plugs.

1. 25 sks at 1950 2. 100 sks at 1100ft. 3. 40 sks at 258. 4. 10 sks at 40 ft.  
15 sks rathole (circ)

Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN) *MJS*

Plugging Operations attended by Agent?: All      Part      None X

Operations Completed: Hour: 7:00PM Day: 11th Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Western Ks. Drilling ordered 190 sks 60/40 poz 6% gel

and cc. 42-45 vis mud. Circ hole. Spotted and displaced cement thru  
drill stem. Heavy mud between all plugs.

1st plug at 1950 w/25 sks cement 4th plug 40 ft. w/10 sks cement

2nd plug at 1100 w/100 sks w/ 1 sk f.c. 15 sks in rathole Circ. Cement by

3rd plug at 258 w/40 sks cement. Halliburton Cement

Remarks: (if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 4-3-91

INV. NO. 31322

*R.S.*

RECEIVED  
STATE CORPORATION COMMISSION

Signed Marion J. Schmidt  
(TECHNICIAN)  
MAR 22 1991

CONSERVATION DIVISION  
Wichita, Kansas

Marion J. Schmidt

FORM CP-2/3  
Rev. 01-84