

6030558

API NUMBER 15-065-22,231-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SUSWSE, SEC. 16, T. 9 S, R. 23 W
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name HICKS Well # 1

Operator: RAINS & WILLIAMSON DRILLING County GRANHAM 130.00

Name & Address 435 PAGE COURT 220 W. DOUGLAS Well Total Depth 4000' feet

WICHITA, KANSAS
67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 3/8 feet 225'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor RAINS & WILLIAMSON DRILLING License Number 63

Address AS ABOVE

Company to plug at: Hour: PM Day: 9 Month: 9 Year: 19 85

Plugging proposal received from LEWIS BURGESS

(company name) RAINS & WILLIAMSON (phone) _____

were: 8 3/8 SET @ 225' w/ 5X. WITH HOLE FULL OF NO LESS THAN 36 GUIS.
MUD. WITH NO LOSS OR GAIN OF FLUID. SPOT CEMENT PLUGS WITH
DRILL PIPE. ORDER 190 SX. 60/40 PZ 6" G. 3" 8 3/8 W.P.
ALLIED CEMENT CO.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1: PM Day: 9 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ 2040' BREAK CIRC. DISPLACE 25 SX.

CMT. MIX. LAYDOWN D.P. TO 950' DISPLACE 100 SX. CMT. MIX. + 1 SX. HULLS
LAYDOWN D.P. TO 220' DISPLACE 40 SX. CMT. MIX. LAYDOWN D.P.
PUSH W.P. TO KELLY DEPTH DUMP 1 SX. HULLS FILL HOLE TO BASE OF
CELLAR W/ 10 SX. CMT. MIX. DISPLACE 15 SX. CMT. MIX. IN RATHOLE
W/ JOINT OF PIPE PLUG COMPLETE

Remarks: ELEV. 2200 ANHY. 2021 TOP K.C. 4000' WATER FROM POND
(if additional description is necessary, use BACK of this form.)

INVOICED
STATE CORPORATION COMMISSION

DATE SEP 17 1985

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 10132

SEP 16 1985

CONSERVATION DIVISION
Wichita, Kansas

9-16-85