

6 050006

8-24

352 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE NE NW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,482-00-00  
SEC. 2 T 9 S, R 24 W/E

4950 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # @%# 3252

Lease Name Keith Well # 2

Operator: Venture Resources  
Name & Address: 518 17th  
1130 Denver Club Bldg  
Denver, Colorado 80202

County Graham 128.83  
Well Total Depth 3964 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Russell, Ks.

Company to plug at: Hour: AM Day: 24 Month: August Year: 19 88

Plugging proposal received from Larry Langhoffer

(company name) Emphasis Oil Operations (phone) \_\_\_\_\_

were: Order 190 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Bruce D. Basye (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 4:30AM Day: 24 Month: August Year: 19 88

ACTUAL PLUGGING REPORT

- 1st plug at 2070' w/25 sks Anhy
- 2nd plug at 1190' w/100 sks 1 sk F.C. (Dakota)
- 3rd plug at 300' w/40 sks
- 4th plug at 40' w/10 sks
- 15 sks in rathole

RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 6 1988  
09-06-1988  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

(XXX/ did not) observe this plugging.

Signed Bruce D. Basye (TECHNICIAN)

INVOICED

DATE 9-8-88

INV. NO. 22172