

4-032360

7-22

15-065-01586-0000

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 9-9-55

SW SW SE /4 SEC. 03 , 09 , 24 W
330 feet from S section line
2310 feet from E section line

Operator license# 100/01

Lease: Ida Keith Well # 5

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990081-004

County: Graham

Well total depth 3960 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 171 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Poe Servicing, Inc. License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: A.M. Day: 22 Month: July Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:00 A.M., Day: 22 Month: July Year: 1999

Actual plugging report: 8 5/8" set at 171' cwc. 5 1/2" set at 3953' w/cement N/A.
Prod Perfs 3935' - 3941'. Critical area control shots at 1200' and 2150'. Squeezed 5 1/2"
with 190 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 800#.
Close in P.S.I. Bled to 0#. Squeezed 8 5/8" annulus with 50 sxs cement blend to Max. P.S.I.
200#. S.I.P. 100#. Plug complete.

Remarks: Allied Cement Company

Condition of casing(in hole): GOOD BAD Any plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1999
08-11-1999
CONSERVATION DIVISION
Wichita, Kansas

Form CP-2/3

R