

4-032362

7-22

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-20,155-00-00

SE NW SW SW /4 SEC. 03, 09, 24 W
825 feet from S section line
4785 feet from E section line

Operator license# 100/01

Lease: Ida Keith Well # A-8

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990081-001

County: Graham
Well total depth 3962 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 265 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Poe Servicing, Inc. License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: A.M. Day: 22 Month: July Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:30 A.M., Day: 22 Month: July, Year: 1999

Actual plugging report: 8 5/8" set at 265' w/225 sxs cwc. 5 1/2" set at 3961' w/75 sxs.
Prod Perfs 3914' - 3920'. Critical area control shots at 1175' and 2125'. Squeezed 5 1/2"
with 300 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 600#.
Close in P.S.I. 200#. Squeezed 8 5/8" annulus with 50 sxs cement blend to Max. P.S.I. Blew
head off top 8 5/8". Plug complete.

Remarks: Allied Cement Company

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

MD

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1999
08-11-1999
CONSERVATION DIVISION
Wichita, Kansas