

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Graham County, Sec. 7 Twp. 9S Rge. 23W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE SE NE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Harvey "B" Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 19, 1957

Application for plugging filed August 19, 1957

Application for plugging approved August 19, 1957


Plugging commenced August 19, 1957

Plugging completed August 19, 1957

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3865 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	8-8-57	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole with 25 sacks cement at 600 feet. Set No. 1 plug at 215 feet with 15 sacks cement. Set No. 2 plug at 40 feet with 10 sacks cement.

STATE CORPORATION COMMISSION  
SEP 5 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Imperial Oil of Kansas, Inc.  
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Raymond L. Bacon  
780 Fourth National Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of September, 19 57

Louetta M. Duncan  
Louetta M. Duncan Notary Public.

My commission expires December 19, 1960

PLUGGING  
FILE SEC. 7 T. 9 R. 23W  
BOOK PAGE 39 LINE 2



15-065-00956-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
780 Fourth National Bldg.,  
Wichita 2, Kansas

Harvey "B" No. 1  
SE SE NE Sec. 7-9S-23W  
Graham County, Kansas

Total Depth: 3865

Elevation: 2302' R.B.  
Production: D & A

Commenced: 8-8-57 Completed: 8-19-57

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 223 feet with 175 sacks cement.

Figures indicate bottom of formations:


Surface Sand & Clay	223'		<u>TOPS</u>	
Shells & Shale	1290'	Heebner	3594'	(-1292)
Dakota Sand	1575'	Toronto	3620'	(-1318)
Shale & Red Bed	1888'	Lansing	3634'	(-1332)
Shale & Shells	1952'	Total Depth	3865'	(-1563)
Anhydrite	1993'			
Shale & Shells	2335'			
Shale	2476'			
Shale & Lime	2480'			
Lime	3865'			
Total Depth	3865'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

9-5-57  
STAT. GUARDIAN DIVISION  
SEP 5 1957  
CONSERVATION DIVISION  
Wichita, Kansas

IMPERIAL OIL OF KANSAS, INC.

By: Raymond H. Inman  
Vice President



Subscribed and sworn to before me this 5th day of September, 1957.

My Commission Expires:

December 19, 1960

Loretta M. Duxan  
Notary Public

PLUGGING  
FILE SEC. 7 T. 9 R. 23W  
BOOK PAGE 39 LINE 2