

15-065-30052-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Harvey

WELL NUMBER 1

_____ Ft. from S Section Line

NE NE NE Ft. from E Section Line

SEC. 7 TWP. 9 RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed 4/25/65

Plugging Commenced 7-22-93

Plugging Completed 7-22-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	222	8 5/8		
	Casing	0	4 1/2	3935		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Perf. 2 shots at 2065' and 1200'. Run tubing openended to 3878 Spot 50 sk. 60/40 pos. 10% gel 150# hulls. Pull to 2837 spot 50 sk 60/40 100# hulls. Pull tubg. to 1765 spot 60 sk. with 150 hulls. Circulate to surface. Hook to annulus mix 50 sk. with 50# hulls. 200# max. pressure 200# shut in. Hook to 4 1/2 mix 75 sk. with 50# hulls. Max. pressure 900#. 500# shut in.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

RECEIVED
STATE CORPORATION COM

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

NOV 03 1993
11-3-93

Mr. Ted Crawford (Employee of Operator) or CONSERVATION DIVISION
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed the
the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 2 day of November, 19 93
ROSEMARY SMITH
My Appt. Exp. 5-1-1995
My Commission Expires: _____

Rosemary Smith
Notary Public
5-1-1995