

15-065-00607-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 12 Twp. 9 Rge. 23 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Sunray M. d-Continent Oil Co.  
Lease Name Mildrexter #1 Well No.  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed Dec. 8, 19 57  
Application for plugging filed June 26 19 58  
Application for plugging approved June 27 19 58  
Plugging commenced 6-28-58 19  
Plugging completed 7- 2-58 19  
Reason for abandonment of well or producing formation  
Uneconomical to operate



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production May 1 19 58  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3930 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	288'	none
				5-1/2"	3929'	3006'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3880' and found it open.  
Filled w/sand to 3825' and ran 4 sacks of cement with dump bailer. Pulled 5 1/2" casing.  
Checked hole with bailer to 340', mudded the hole to 280', set a 10' rock bridge and ran 25 sacks of cement. Mudded the hole to 40' set a 10' rock bridge and ran 10 sacks of cement to base of cellar.

Log attached.


RECEIVED  
STATE CORPORATION COMMISSION  
JUL 9 1958  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor WEST SUPPLY CO., INC. 7-9-58  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
N. E. Montgomery (employee of owner) or (owner/operating) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery  
Box # 788, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of JULY, 19 58



Thomas V. Boyce  
Notary Public.

PLUGGING  
FILE SEC. 12 T. 9 R. 23W  
BOOK PAGE 110 LINE 39

15-065-00607-00-00

Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
December 3, 1957

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: November 20, 1957  
Drilling Completed: November 30, 1957

Frank Mildexter #1 E/2 of  
SW of Sec. 12-9S-23W,  
Graham County, Kansas.

DRILLERS LOG

Depth Figures indicate base of formation:

Surface	0
Shale & Shells	1075
Sand & Shale	1380
Shale & Shells	1925
Red Bed & Shale	2002
Anhydrite	2035
Shale & Shells	2100
Shale & Lime	2525
Lime & Shale	2730
Lime	2845
Lime & Shale	3185
Shale & Lime	3305
Lime & Shale	3455
Shale & Lime	3530
Lime & Shale	3687
Lime	3855
Lime & Shale	3872
Lime	3930 TD

L-KC

1-9-58

I, Frank E. Stickle hereby certify the above to be a true and complete  
Drillers Log of Sunray Mid-Continent Oil Company's Frank Mildexter #1  
E/2 of SW of Section 12-9S-23W, Graham County, Kansas.

*Frank E. Stickle*  
Frank E. Stickle

*Lillian T. Bonham*  
Notary Public

February 13, 1960  
My Commission Expires

PLUGGING  
FILE SEC 12 T 9 R 23W  
BOOK PAGE 110 LINE 39