


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 12 Twp. 9S Rge. (E) 23 (W)
Location as "NE/CNW&SW" or footage from lines NW NW NW
Lease Owner Petroleum Management, Inc. for Transit Corporation
Lease Name Mildrexter Well No. 1
Office Address 1019 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 9-4 1955
Application for plugging filed 8-30 1957
Application for plugging approved 9-3 1957
Plugging commenced 10-2 1957
Plugging completed 10-10 1957
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 8-9 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation Lansing, K.C. Depth to top 3652 Bottom 3869 Total Depth of Well FB 3860 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Lansing, K.C.</u>	<u>Oil</u>	<u>3616</u>	<u>3618</u>	<u>5-1/2"</u>	<u>3890'</u>	<u>1844'</u>
				<u>8-5/8"</u>	<u>175'</u>	<u>None.</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3800' with sand, dumped four sacks cement with bailer. Shot pipe off at 1844'. Pulled pipe to 1000' and circulated seven sacks mud, pulled pipe to 700' dumped 25 sacks cement, pulled pipe to 60' and dumped 15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1957
CONSERVATION DIVISION
Wichita, Kansas

10-22-57

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E & L Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John W. Ritchey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John W. Ritchey
1019 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of October, 1957

Maurice C. Murphy
Notary Public.

My commission expires April 23, 1958.



PLUGGING
FILE SEC. 12 T. 9 R. 23
BOOK PAGE 41 LINE 14

TRANSIT CORPORATION - OIL TRADING ASSOCIATES, INC.

MILDREXTER "A" #1

NW NW NW Section 12-9S-23W, Graham County, Kansas

Elevation: 2354 D.F.

Commenced: 8-17-55

Completed: 8-30-55

<u>Formation</u>	<u>From</u>	<u>To</u>
Clay	0	75
Shales & Shells	75	110
Clay	110	175
Shale & Shells	175	1950
Anhydrite	1950	1985
Shale	1985	2250
Shale-Lime Shells	2250	2500
Lime & Shale	2500	3075
Lime & Shale	3075	3560
Lime	3560	3891
		3891 T.D.

Formation Tops

Topeka	3388
Heebner	3614
Toronto	3640
Lansing-Kans. City	3652
Base-Kansas City	3869
Total Depth	3891

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

TRANSIT CORPORATION

By C. W. Dodson
C. W. Dodson

Subscribed and sworn to before me this 13th day of July, 1956.

My commission expires Mar. 31, 1960.

James C. Perry
Notary Public

PLUGGING
 FILE SEC 12.T.9 R.234
 BOOK PAGE 37 LINE 14

RECEIVED
 STATE CORPORATION COMMISSION
 2-158
 FEB. 1 1958
 CONSERVATION DIVISION
 Wichita, Kansas