

15-065-00737-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 13 Twp. 9 Rge. 23 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW 1/4, SW 1/4, NW 1/4
Lease Owner Transit Corporation
Lease Name Marshall Law "A" Well No. 1
Office Address 1516 Liberty Bank Bldg., Okla. City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-11 19 55
Application for plugging filed 9-11 19 55
Application for plugging approved 9-11 19 55
Plugging commenced 9-11 19 55
Plugging completed 9-11 19 55
Reason for abandonment of well or producing formation _____



If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 146' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 140' with heavy drilling mud, set plug and cemented to bottom of cellar by pumping in 50 sacks cement by service company.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1955
CONSERVATION DIVISION
Wichita, Kansas


9-16-55

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Bldg., Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
C. W. Dodson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Dodson
Oklahoma City, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 15th day of September, 19 55
Jane A. Brady Notary Public.
My commission expires Jan. 28, 1959.



PLUGGING
FILE SEC-13 T-9 R-23W
BOOK PAGE 149 LINE 26

TRANSIT CORPORATION
Oklahoma City, Oklahoma
Driller's Log
Marshall Law "A" #1
SW SW NW Sec. 13-9S-23W
Graham County, Kansas

Elevation: 2348 R. B.
Commenced: 8-31-55
Completed: 9-10-55

| <u>Formation</u> | <u>From</u> | <u>To</u> | |
|------------------|-------------|-----------|--|
| Clay | 0 | 60 | |
| Shale & Shells | 60 | 146 | 146' of 8-5/8" Csg. cem. w/ 100 sacks cement. |
| Shale & Shells | 146 | 1935 | |
| Anhydrite | 1935 | 1960 | |
| Red Bed & Shale | 1960 | 2125 | |
| Shale | 2125 | 2410 | |
| Lime & Shale | 2410 | 2750 | |
| Lime | 2750 | 2900 | |
| Lime & Shale | 2900 | 3080 | |
| Lime | 3080 | 3140 | |
| Shale & Lime | 3140 | 3620 | |
| Lime | 3620 | 3725 | |
| Lime & Shale | 3725 | 3779 | |
| Lime | 3779 | 3900 | |

| T. D. | Sample Tops | |
|----------|-------------|-------|
| Topeka | 3389 | -1041 |
| Heebner | 3616 | -1268 |
| Toronto | 3640 | -1292 |
| Lansing- | | |
| K. C. | 3653 | -1305 |
| Base KC | 3872 | -1524 |
| T.D. | 3900 | -1552 |

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

TRANSIT CORPORATION

BY *C. W. Dodson*
Office Mgr.

Subscribed and sworn to before me this 15th day of September, 1955.

James A. Brady
Notary Public
State of Oklahoma.

My commission expires Jan. 28, 1959.

9-16-55

PLUGGING
FILE SEC. 13 T. 9 R. 23W
BLOCK PAGE 149 LINE 26