

15-065-00780-00.00

WELL PLUGGING RECORD

NORTH

		X
	16	

Locate well correctly on above
Section Plat

GRAHAM County. Sec. 16 Twp. 9S Rge. 23W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NW NE
Lease Owner WOOD RIVER OIL & REFINING CO., INC.
Lease Name SCHWEITZER Well No. 1
Office Address 321 West Douglas, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 9-5-59 19
Application for plugging filed 9-5-59 19
Application for plugging approved 9-5-59 19
Plugging commenced 9-5-59 19
Plugging completed 9-5-59 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricious
Producing formation Depth to top Bottom Total Depth of Well 3915' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	246'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 550' set plug &
cemented with 20 sx cement thru drill pipe.
Filled with heavy mud to 240' set plug
& cemented with 20 sx cement thru drill
pipe. Filled hole with heavy mud to 40'
set solid bridge with 10 sx cement to
base of cellar. Job complete 9-5-59.


RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E DRILLING, INC. 9-15-59
Address 719 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott, K & E DRILLING, INC.
719 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of September, 19 59
My commission expires August 11th, 1962.




Patricia M. Edwards, Notary Public.

PLUGGING

File Sec. 16 T. 9 R. 23W
Book Page 3 Line 22

DRILLER'S WELL LOG

Company: WOOD RIVER OIL & REFINING CO.
OPERATOR: WOOD RIVER OIL & REFINING CO., INC.
321 West Douglas
Wichita, Kansas
Total Depth: 3915
Comm. 8-29-59
Shot or Treated.
CONTRACTOR: K & E DRILLING, INC.
719 UNION CENTER BLDG.
WICHITA, KANSAS
Issued. 11-7-59
SEC. 16 T. 9 R. 23W
WELL NAME: NE 1/4 SCHWEITZER
LOCATION: NE NW NE, 16-9S-23W
County: GRAHAM COUNTY, KANSAS
COMMENCED: 8-29-59
COMPLETED: 9-5-59
Elevation: 2347'
ELEVATION: unknown
Product on: Dry
PRODUCTION: D & A



ROTARY TOTAL DEPTH: 3915 Figures indicate Bottom of Formation

surface soil & clay 8
sand 30
shale & shells 246
shale 1475
sand 1030
shale & red bed 1475
shale & sand 1915
sand 1720
red bed 1875
Anhydrite 2015
shale & shells 2570
shale & lime 2740
lime & shale 2870
lime 3165
shale & lime 3335
lime & shale 3460
lime 3662
Total Depth 3915
TOPS: SCOUT
Anhydrite
Reebner
Toronto
Lansing

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

R.T.D.

8
30
246
955
1080
1475
2510
2720
1975
2015
2570
2740
2870
3165
3335
3460
3885
3915
3915

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1959
CONSERVATION DIVISION
Wichita, Kansas

11-19-59

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Dale Silcott, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott

Dale Silcott
September 11th, 1959

Notary Public.

Patricia M. Edwards



15-065-00780-00-00
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


COPY

Company- WOOD RIVER OIL & REFINING CO.
Farm- Schweitzer No. 1

SEC. 16 T. 9 R. 23W
NE NW NE

Total Depth. 3917'
Comm. 8-29-59 Comp. 9-5-59
Shot or Treated.
Contractor. K & E Drlg.
Issued. 11-7-59

County Graham
KANSAS



CASING:

8 5/8" 246' cem w/175 sx.

Elevation. 2347'

Production. Dry

Figures indicate Bottom of Formations.

surface soil & clay	8
sand	30
shale & shells	246
shale	955
sand	1080
shale & red bed	1475
shale & sand	1510
sand	1720
red bed	1975
Anhydrite	2015
shale & shells	2570
shale & lime	2740
lime & shale	2870
lime	3165
shale & lime	3335
lime & shale	3460
lime	3885
lime & shale	3915 RTD
lime & shale	3917
Total Depth	

TOPS: SCOUT

Anhydrite	1975
Heebner	3638
Toronto	3662
Lansing	3676

RECEIVED
STATE CORPORATION COMMISSION

2-22-66
FEB 22 1966

WICHITA, KANSAS