


15-065-01071-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

GRAHAM County. Sec. 16 Twp. 9 Rge. 23 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines SE SW NE
Lease Owner MOBLE C. HOOVER
Lease Name SCHWEITZER Well No. #1
Office Address 110 W. ELM ST., EL DORADO, ARKANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed OCTOBER 15 19 64
Application for plugging filed OCTOBER 15 19 64
Application for plugging approved OCTOBER 15 19 64
Plugging commenced 1:30 A.M. OCTOBER 16 19 64
Plugging completed 4:30 A.M. OCTOBER 16 19 64
Reason for abandonment of well or producing formation DRYHOLE

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY, HAYS, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3945 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	220	7"	220	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED W/15 SACKS CEMENT @ 550',
15 SACKS CEMENT @ 200', 10 SACKS
CEMENT @ 40' TO SURFACE

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1964

CONSERVATION DIVISION
Wichita, Kansas

10-21-64

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor CHEMICAL & TECHNICAL SERVICES, INC.
Address P.O. BOX D, HILL CITY, KANSAS

STATE OF KANSAS COUNTY OF GRAHAM, ss.
DANIEL F. MCCARTHY (employee of ~~owner~~ ~~owner~~ ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) D. F. McCarthy
P.O. BOX D, HILL CITY, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of October, 1964

My Commission Expires January 20, 1968

My commission expires _____

Carla J. Sleser
Notary Public.



15-065-01671-00-00

CONTRACTOR'S WELL LOG

CONTRACTOR:	CHEMICAL & TECHNICAL SERVICES, INC.
OWNER:	MOBLE C. HOOVER
WELL:	SCHWEITZER #1
LOCATION:	SE SW NE SEC. 16-9S-23W GRAHAM CO., KANSAS
COMMENCED:	10/8/64
COMPLETED:	10/16/64

0	40	CLAY & ROCK
40	90	SAND
90	100	CLAY
100	221	BLUE SHALE
221	1560	SHALE & SAND
1560	1760	SAND
1760	2016	SHALE & RED BED.
2016	2045	ANHYDRITE
2045	2390	SHALE & SAND
2390	3728	SHALE & LIME
3728	3945	LIME
3945		ROTARY TOTAL DEPTH

SET 7" SURFACE CASING @ 220' w/105 SACKS CEMENT

DRY & ABANDONED

WE HEREBY CERTIFY THIS TO BE A CORRECT AND ACCURATE LOG OF THE ABOVE DESCRIBED WELL, AS SHOWN ON THE DAILY DRILLING REPORTS.

CHEMICAL & TECHNICAL SERVICES, INC.

BY: *D. F. McEntly*
ASST. TREASURER

SUBSCRIBED AND SWORN TO BEFORE THIS 20th DAY OF OCTOBER, 1964.

Bank of America
Notary Public
Commission Expires January 20, 1968

Carroll Dyer Cox
NOTARY PUBLIC