

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-065-21698-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 19 TWP. 9S RGE. 23 /E/W
 Location as in quarters or footage from lines:
C W/2 NW NW

Lease Owner Yost Oil Operations
 Lease Name Hilderbrand Well No. 1
 Office Address P. O. Box 811, Russell, KS 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 9-27-82
 Application for plugging filed 9-27-82
 Plugging commenced 9-27-82
 Plugging completed 9-28-82

Locate Well
 correctly on above
 Section Platt.

Reason for abandonment of well or producing formation
Dry Hole

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3984'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	270'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Mud laden fluid @ 3984' - 2100'
20 sks cement @ 2100'
100 sks cement @ 1250'
40 sks cement @ 280'
10 sks cement @ 40'
10 sks cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Joe K. Branum (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
P. O. Box 506, Russell, KS 67665
 (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 82

Glenda R. Tiffin
 Glenda R. Tiffin, Notary Public
 STATE CORPORATION COMMISSION

My Commission expires: February 6, 1984



RECEIVED
 CONSERVATION DIVISION
 Wichita, Kansas

10-1-82

15-065-21698-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 01 1982
10-1-82

EMPHASIS OIL OPERATIONS
P. O. Box 506
Russell, Kansas 67665

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

OPERATOR: Yost Oil Operations
P. O. Box 811
Russell, Kansas 67665

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, Kansas 67665

LEASE: Hilderbrand WELL: #1

LOCATION: C W/2 NW NW
Section 19-9S-23W
Graham County, Kansas

Total Depth: 3984'

Elevation:

Commenced: 9-21-82

Completed: 9-28-82

Casing: 8-5/8" @ 270' with 160 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & Sand	30'	Anhydrite	2110'
Sand & Shale	278'	Shale & Lime	2251'
Sand	1010'	Shale	2448'
Shale & Sand	1600'	Shale & Lime	3810'
Shale	1814'	Lime (R.T.D.)	3984'
Sand	2072'		


STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Joe K. Branum

Joe K. Branum

Subscribed and sworn to before me this 30th day of September, 1982,
My Commission Expires: February 6, 1984.



Glenda R. Tiffin

Notary Public