



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-065-~~1589~~²⁰²⁴⁶-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Warren Davis of Hellar Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Landes Explorations Company & Franks Petroleum Co.,

Complete Address: P. O. Box #867, Magnolia, Arkansas.

Lease Name: Dreiling Well No. 1

Location: NE-NW-NE Sec. 19 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 3862' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

216'--8 5/8" surface casing, cement circulated with 150 Sx. Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1270' and displace 100 Sx. cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
87-23-1969
JUL 23 1969
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

W. L. Pickels
Conservation Division Agent