



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1963
 08-14-1963
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-02640-00-00

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. A. G. Leinmiller of Abercrombie Drilling Inc., has this date requested permission to plug the following described well:

Mr. Leinmiller guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Nicholson Well No. 1

Location: CNE-SE Sec. 22 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4065 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Leinmiller was instructed to plug the well as follows:

209' -- 8 5/8" Surface pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx cement.

" " 190' with 1/4 sk hulls & 20 Sx cement.

" " 40' with 1/2 Sk hulls & 10 Sx cement.

Very truly yours,

A. L. Nichols
 Conservation Division Agent