



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1973  
01-08-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20581-00-00

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company,

Complete Address: 217 North Water, Wichita, Kansas.

Lease Name: Ronald Nickelson Well No. 1-V

Location: CNW-NE Sec. 22 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4035' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

260'--10 3/4" Surface casing, cement circulated with 150 Sx. (9" hole from base of surface to 2100'. 77/8" hole from 2100' to TD). Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 150 Cu. Ft. cement thru DP. Pull DP to 275' and displace 40 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1 sack hulls and 15 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*R. L. Nichols*  
Conservation Division Agent