



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 31 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
03-31-1971

15-045-20423-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mickelson of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Mickelson guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling and Petroleum Resources,

Complete Address: P. O. Box #18407, Wichita, Kansas.

Lease Name: Engleman Well No. 1

Location: NW-SW-SE Sec. 24 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 3911' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Mickelson was instructed to plug the well as follows:

258'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1075'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*H. L. Nichols*

Conservation Division Agent