



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

September 3, 1981

15-065-21458-00-00

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Frank Deenihan of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: J. B. & E. Oil and Edward P. Leiker

Complete Address: Route 17, Box 190, Hays, Kansas 67601

Lease Name: Werth "B" Well No. 1

Location: SW SE NW Sec. 26 Twp. 9 Rge. 25 NE (W)

County: Graham Total Depth: 4150'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Deenihan was instructed to plug the well as follows:

8-5/8"-251'-165 sacks common 2% gel and 3% CC Anh. 2235-2270' Elev. 2560 GL

Circulate hole wnd fill with mud. Pump 70 sacks cement through drill

pipe at 2020'. Pump 60 sacks cement through drill pipe at 310'. Fill

hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with

10 sacks cement. Cement rathole with 10 sacks cement.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
09-02-1981
SEP - 9 1981
CONSERVATION DIVISION
Wichita, Kansas