



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1968
CONSERVATION DIVISION
Wichita, Kansas

01-15-1968

15-065-20111-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Flake of Woodman-Iannitti Drlg. Co., has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Allison & Black,

Complete Address: 1415 Plaza Building, Wichita, Kansas.

Lease Name: Schilling Well No. 1

Location: SE-SE-NE Sec. 30 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4125 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

208'--8 5/8" Surface pipe, cement circulated with 130 Sx.
Dakota section from 1125' to 1300'.

Circulate hole with heavy mud. Pull DP to 1325' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent