



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas

10-4-1971

15-065-20489-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Werth Well No. 1

Location: NE-SW-NW Sec. 30 Twp. 9 Rge. (E)(W)25

County: Graham Total Depth 4155' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

227'--8 5/8" Surface casing, cement circulated. (6 3/4" Hole).
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 70 Sx. cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. D. Dickler
Conservation Division Agent