



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
02-29-1968

15-065-20125-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sonny Denning of Dean & Clark, Incorporated, has this date requested permission to plug the following described well:

Mr. Denning guarantees payment of the plugging fee.

Operator's full Name: Dean & Clark, Incorporated,

Complete Address: 416 Union Center Building, Wichita, Kansas.

Lease Name: Werth Well No. 1

Location: NE-NE-SW Sec. 31 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4105' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Denning was instructed to plug the well as follows:

210'--8 5/8" Surface pipe, cement circulated with 160 Sx.  
Dakota section from 1000' to 1350'.

Circulate hole with heavy mud. Pulled DP to 1380' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent