



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-065-01635 - 00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas
04-04-1972

Dear Sir:

Mr. Albert Unruh of South-West Csg. Pulling, Inc., has this

date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Bankoff Oil Company,

Complete Address: 1119 Sherman, Great Bend, Kansas.

Lease Name: Brungardt Well No. 1

Location: 150 No. of CNW-NW Sec. 33 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4055' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

240'--8 5/8" Surface casing, cement circulated with 150 Sx.

4045'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4034'. Top perforations from 3872' to 3876'.

Push plug to 3850', sand back to 3825' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent