



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-065-62037-00-00

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 14 1964
 09-14-1964
 CONSERVATION DIVISION
 Wichita, Kansas
 has this

Dear Sir:

Mr. Junior Gideon of Kimbark Exploration Co.,

date requested permission to plug the following described well:

Mr. Gideon guarantees payment of the plugging fee.

Operator's full Name: Kimbar Exploration Co.,

Complete Address: 201 University Blvd., Denver, Colorado.

Lease Name: Mary Well No. 1

Location: SW-NE Sec. 33 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4100 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gideon was instructed to plug the well as follows:

195'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 600' & 20 Sx. cement.

" " 180' with 1/4 sk hulls & 20 Sx. cement.

" " 40' with 1/2 sk hulls & 10 Sx. cement.

Very truly yours,

W. A. Nichols
 Conservation Division Agent