



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

12-22-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20288-00-02

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Leben-Bankoff,

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Brungardt Well No. 4

Location: CS/2-N/2-NW Sec. 33 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4070' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent