



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 4 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas

04-04-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir: 15-065-30203-00-00

Mr. Albert Unruh of South West Casing Pulling, Inc has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Bankoff Oil Company,

Complete Address: 1119 Sherman, Great Bend, Kansas.

Lease Name: Brungardt Well No. 2

Location: CNE-NW Sec. 33 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4035' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

201'--8 5/8" Surface casing, cement circulated with 150 Sx.

3935'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3907'. Top perforations from 3857' to 3861'.

Sand well back to 3840' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

R. L. Nichols  
Conservation Division Agent