

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-179-30000-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1965
02-10-1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Bert Self Casing Pulling has this

date requested permission to plug the following described well:

Raymond Oil Co., Inc.,

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Incorporated,

Complete Address: 410 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Minium Well No. 1

Location: CNW-NW Sec. 4 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4010 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Self was instructed to plug the well as follows:

228'--8 5/8" Surface pipe, cement circulated with 200 Sx.

3983'--5 1/2" production casing cemented with 150 Sx.

Sand well back to 3960' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing to 600' and circulate heavy gel mud, Pull 5 1/2"
to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 210'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ XXX
@ 30' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent