

6070166

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,958-00-00

SE 1/4, SEC. 12, T. 9 S, R 24 (M)

880 feet from N(S) section line

2200 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7916

Lease Name HILDEBRAND Well # 1

Operator Name: ELDON J. SCHIERLING

County GRAHAM

Address 850 JUTTON PLACE

Well Total Depth 4005 ^{130.16} feet

WICHITA, MS. 67202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____ # 179

Plugging Contractor ABERCROMBIE DRUG, INC. License Number 5422 TAG

Address 801 UNION CENTER, WICHITA, KANSAS. 67202

Company to plug at: Hour: 11:30 PM Day: 10th Month: JUNE Year: 19 84

Plugging proposal received from HAROLD MALEY.

(company name) ABERCROMBIE DRUG, INC. (phone) 216-267-0042

were: 8 5/8" - 217^{ft} SP. CUL #165^{SK} COMMON - GEL - CA-CL - BY SUN OMT.

ORDER 165^{SK} COMMON - GEL - CA-CL - 1^{SK} CELE - AND 8 5/8" PLUG

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS

MUD VISCOSITY 50 - WEIGHT 9.5^{lbs} EIV. 2406^{ft} - ANH. 2067

NO AIRBUCKLE - KC - WELL - NO CIRCULATION PROBLEMS.

Plugging Proposal Received by Merton Schmidt (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 AM Day: 11th Month: JUNE Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 195^{SK} 50 Pozmix GEL - CA-CL - 1^{SK} CELE TO 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS

1st plug @ 2100^{ft} #25^{SK} OMT, - 2nd plug @ 1230^{ft} #100^{SK} OMT #10^{SK} CELE

3rd plug @ 270^{ft} #50^{SK} OMT, - 4th plug ^{SOLID BRIDGE} HULLS - PLUG @ 40^{ft} #50^{SK} OMT

10^{SK} RAT HOLE (CIRCULATE) CEMENTED BY SUN OMT

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____ (if additional description is necessary use BACK of this form.)

INVOICED

JUN 18 1984

CONSERVATION DIVISION
Wichita, Kansas

Merton Schmidt (TECHNICIAN) DOIC

DATE 6-25-84

INV. NO. 2127 6-11