

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20855-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 26-9S-25W
702 feet from S Section Line, 3442 feet from E Section Line
Lease/Unit Name: SPIES Well Number: 1
County: GRAHAM Total Vertical Depth: 4130 feet

Operator License No.: 9067
Operator Name: DAMAR RESOURCES, INC.
Address: PO BOX 70
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 269
Production: Size 5.5 feet: 4129
Liner: Size feet: 134.23

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/5/00
Plug Co. License No.: 9067 Plug Co. Name: DAMAR RESOURCES, INC.
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed Plugging Method: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/05/2000 2:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 269' w/200 sxs. 5 1/2" set at 4129' w/125 sxs.
Prod.Perfs 3947' - 4058'. Bad casing at T.O.C.
Squeezed 5 1/2" w/265 sxs with 500# hulls mixed in to Max. P.S.I. 800#.
Squeezed 8 5/8" w/50 sxs to Max. P.S.I. 500#. Held. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 2000
09-25-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks:

Plugged through:

District: 04

Signed Carl Goodrow
(TECHNICIAN)

KCC

INVOICED

Form CP-2/3

SEP 18 2000

DATE 9/26/00

HAYS, KS

WELL NO. 2001060749

THE MAURICE L. BROWN CO. &
 I. WAYNE WOOLSEY #1 SPIES 26-9-25W
 1500 VICKERS-KSB&T BLDG., WICHITA, KS. 702' FSL &
 CONTR ABERCROMBIE DRG., INC. CTY GRAHAM 1838' FWL, SW

GEOL _____ FIELD EMOR NE

E 2578 KB CM 8/13/76 CARD ISSUED 12/16/75 P 28 BOPD + 100BWPD
 LANS 3947-49 & 4054-58

API 15-065-20,855

LOG	TOPS	DEPTH	DATUM
ANH		2218	+ 360
B ANH		2251	+ 327
HEEB		3838	-1260
TOR		3860	-1282
LKC		3871	-1293
BKC		4108	-1530
TD		4130	-1552

8-5/8" 269/200sx, 5 1/2" 4127/125sx
 DST (1) 3946-65/45-45-45-45, 440' GIP,
 100' O&GCM, 120' EMUL OGM, 250' HO&GCM
 50' GMW W/SPKS 0, 300' SMSW, SIP 741-
 706# FP 24-213# 284-320#
 DST (2) 4021-4040/45-45-90-90, 430' SMSW
 SIP 853-853# FP 36-127# 127-236#
 DST (3) 4052-65/45-45-90-90, 120' GIP, 45'
 SOCM, SIP 109-181# FP 18-36# 36-36#
 DST (4) 4069-88/45-45-45-45, 1' M, SIP 36-
 36# FP 27-36# 18-18#
 DST (5) 3990-4023 (W/SP)/45-45-90-90, 300'
 MSW, SIP 827-827# FP 17-83# 83-199#
 DST (6) 3936-60 (W/SP)/45-45-90-90, 150'
 GIP, 90' SOCM, SIP 794-794# FP 17-33#
 33-50#

INDEPENDENT OIL & GAS SERVICE
 WICHITA KANSAS