

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20875-00-00
Spot: CSWSW Sec/Twnshp/Rge: 26-9S-25W
660 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: SPIES Well Number: 2
County: GRAHAM Total Vertical Depth: 4115 feet

Operator License No.: 9067
Operator Name: DAMAR RESOURCES, INC.
Address: PO BOX 70
HAYS, KS 67601

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 252
Production: Size 5.5 feet: 4115 **133,74**
Liner: Size _____ feet:

9/5

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 9/5/00
Plug Co. License No.: 9067 Plug Co. Name: DAMAR RESOURCES, INC.
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed Plugging Method: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/05/2000 3:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 252' w/190 sxs cwc. 5 1/2" set at 4115' w/135 sxs.
D.V. 2205' w/500 sxs cwc.
Prod.Perfs 3759' - 4050'.
Squeezed 5 1/2" w/340 sxs w/500# hulls mixed in to Max. P.S.I. 500#.
Held. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 2000
09-25-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks:

Plugged through:

District: 04

Signed Carl Goodrow
(TECHNICIAN)

INVOICED

DATE 9/26/00

TRK. NO. 2001060749

SEP 18 2000

THE MAURICE L. BROWN CO. &
I. WAYNE WOOLSEY

#2 SPIES

26-9-25W
C SW SW

1500 VICKERS-KSB&T BLDG., WICHITA, KS.
CONTR ABERCROMBIE DRG., INC. CTY GRAHAM

GEOL RAY PALMER FIELD EMOR NE

E 2552 KB CM 10/30/76 ^{CARD} ISSUED 12/16/76 IP P 80 BOPD

LANS 4046-50

API 15-065-20,875

+	+
+	+
+	+

LOG	TOPS	DEPTH	DATUM
ANH	2190	+ 362	
B ANH	2224	+ 328	
TOP	3591	-1039	
HEEB	3807	-1255	
TOR	3830	-1278	
LANS	3841	-1289	
BKC	4076	-1524	
MARM	4103	-1551	
TD	4206	-1654	

8-5/8" 252/190sx, 5 1/2" 4116/150sx
DST (1) 3836-69/45-45-45-60, 1380' SMCSW
SIP 635-642# FP 60-508# 515-599#
DST (2) 3872-84/60-60-60-120, 140' WM,
SIP 348-340# FP 26-60# 60-85#
DST (3) 3879-2909/60-60-60-120, 360' MW
SIP 611-602# FP 43-136# 136-212#
DST (4) 3910-3921/60-60-60-120, 17' DM
SIP 26-26# FP 13-13# 13-13#
DST (5) 3922-30/60-60-60-120, 230' MW
SIP 848-839# FP 26-68# 68-119#
DST (6) 3972-3990/60-60-60-120, 45' SOSM
SIP 619-662# FP 26-34# 34-43#
DST (7) 3997-4010/60-60-60-120, 50' GIP
70' OCGM, SIP 136-442# FP 21-26# 26-34#

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS