

6 030370

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-0165-22056-00-00  
CNWSW, SEC. 26, T. 9 S, R. 25 WE

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

Operator License # 5252

Lease Name SPIES Well # 1

Operator: R.P. NIXON

County GRAHAM 133.87

Name & Address 207 W. 12TH.

Well Total Depth 4119 feet

HAYS, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67601

Surface Casing: Size 8 5/8 feet 212" / 165 sq.

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor AKLIED CEMENT CO License Number \_\_\_\_\_

Address PLAINVILLE KANSAS

Company to plug at: Hour: PM Day: 19 Month: 12 Year: 19 84

Plugging proposal received from LEON JACOBS

(company name) R.P. NIXON (phone) \_\_\_\_\_

were: 4 1/2 SP @ 4119 WITH 125 sq. Plugback 4108. Top Perf 3953 - Bottom 4045

with bailer 4 1/2" com. can. Sand Dumped to 3850 with 4 1/2" com. can on top with bailer.

Shot off at 3060' and recovered 4 1/2" casing.

Ordered 170 sp 5 1/2" sp 6" bail 3 1/2" - 40 sp. gel. - 300# of hulls. - 1-8 3/8" upper Plug

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:45 PM Day: 19 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT Bottom Plug - With bailer 4 1/2" com. can. Sand dumped to 3850' -

4 1/2" com. can. with bailer on top.

Top Plug - Pumped down 8 5/8" sp. with 300# Hulls - 23 sq. gel - 100 sp. can. mix

170 sp. gel - 8 3/8" plug - 70 sp. can. mix.

100 sp. can. across Dakota section 70 sp. to cover from below S.P. to bottom collar

with gel spacer

Remarks: \_\_\_\_\_

(if additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 07 1985  
01-07-1985  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (did not) observe this plugging.

Signed Carl Goodrow  
(TECHNICIAN)

DATE 1-15-85

INV. NO. 6435

Jan 4 1985  
img  
4