

4-061227

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-179-21,101-0000
260'E.of
N2 NE /4 SEC. 02, 09 S, 26 W
4620 feet from S section line
1060 feet from E section line

Operator license# 6622

Lease: Simon Well # 02

Operator: Jason Oil Company

County: Sheridan 129.06

Address: P.O. Box 701
Russell, Kansas 67665

5/13

Well total depth 3971 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 253 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: Discovery Drilling Company License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:00 P.M. Day: 13 Month: May Year: 2000

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone: -

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 2000
05-18-2000
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 4:00 P.M., Day: 13, Month: May, Year: 2000

Actual plugging report:

1st. Plug at 2200' w/25 sxs cement. Anhydrite 2170' - 2213'.

2nd. Plug at 1250' w/ 100 sxs cement. Dakota 941' - 1241'.

3rd. Plug at 305' w/ 40 sxs cement. Surface pipe to 253'.

4th. Plug at 40' w/10 sxs cement.

Rathole with 15 sxs.

Mousehole with 10 sxs.

Remarks: Allied Cementing.

Condition of casing in hole): GOOD X BAD _____ Anhy.plug: YES _____ X _____ NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING _____, CASING _____. Elevation: 2516 GL

I did[] / did not[X] observe the plugging.

[Signature]
DH (agent)
Form CP-2/3

INVOICED
DATE 5/19/00
INV. NO. 61756

[Signature]