

4-032403

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-179-21052-0000

NE _____ /4 SEC. 02 , 09 , 26 W
4940 feet from S section line
1720 feet from E section line

Operator license# 6622

2/29

Lease: Simon Well # 146.15
Simon

Operator: Jason Oil

County: Sheridan

Address: 363 W. 12th Street
PO. Box 701
Russell, Kansas 67665

Well total depth 497 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Pfeifer Well Service License# Rig Tag 3821

Address: Morland, Kansas 67650

Company to plug at: Hour: A.M. Day: 29 Month: February Year: 2000

Plugging proposal received from: J.L. Schoenberger

Company: Jason Oil Phone:

Were: Order 250 sxs Mid-Con 2 - Swift Cement.
Use tubing as a work string to plug.
Emergency plug with rig over the hole.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:00 A.M., Day: 29 Month: February, Year: 2000

Actual plugging report: 8 5/8" set at 250' cwc. 5 1/2" set at 4497' with N/A sxs.
Perf at 1250' and 600' with 375 sxs cement with hills cwc. Prod. Perfs at 3720' - 3814'.
Holes in 5 1/2" casing at 3300' and 2500'. Ran tubing to fish at 3300'. Displaced 50 sxs
cement blend with 300# hulls. Pulled tubing to 2200'. Displaced 50 sxs with 300# hulls
mixed in. Pulled tubing to 1500' cwc - 120 sxs. Laid down tubing - topped off with 15 sxs.
Used total 235 sxs with 800# hulls.

Remarks: Anhy 1978' - 2210'.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 2542 GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE 3/15/00
INV. NO. 061434

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 2000
03-15-2000
CONSERVATION DIVISION
Wichita, Kansas

R

SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

Invoice

DATE	INVOICE #
2/28/00	2140

15-179-21052-00-00

BILL TO
Jason Oil Company PO Box 701 Russell, KS 67665-0701

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	1	Simmon	Sheridan		Oil	Workover	Lenny	Squeeze hole

PRICE REFERE...	DESCRIPTION	QTY	UNIT PRICE	AMOUNT
575W	Milage	70	2.00	140.00T
576W-P	Pump Charge - PTA	2	450.00	900.00T
581W	Service Charge Cement	250	1.00	250.00T
583W	Drayage	814.1	0.75	610.58T
330	Swift Multi-Density	235	9.50	2,232.50T
275	Cotton Seed Hulls	8	15.00	120.00T
	Subtotal			4,253.08
Discount	10% Discount		-10.00%	-425.31
	Subtotal			3,827.77
	Sales Tax		4.90%	187.56

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 2000

CONSERVATION DIVISION
Wichita, Kansas

Thank you for your business.	Total	\$4,015.33
------------------------------	--------------	------------