

To: **6 100382**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION S/2 N/2 SE, SEC. 3, T. 9 S, R. 26 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-16
API NUMBER **15-** 179-20,940 - **00-00**

TECHNICIAN'S PLUGGING REPORT

Operator License # 6861
Operator: Ron's Oil Operations Inc.
Name & Address Box 194
Penokee, Ks. 67659

4290 feet from S section line
1320 feet from E section line
Lease Name Sheehan Well # 1
County Sheridan **131.95**
Well Total Depth 4060 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 242

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241
Address Russell, Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Tom Alm
(company name) Emphasis (phone) _____

- were: Spot through drill pipe w/heavy mud between all plugs.
1st plug at 2260' w/25 sks
2nd plug at 1350' w/100 sks
3rd plug at 290' w/40 sks
4th plug at 40' w/wiper plug and 10 sks

RECEIVED
STATE CORPORATION COMMISSION
05-15-1989
MAY 15 1989
CONSERVATION DIVISION
Wichita, Kansas

rathole 15 sks mousehole 10 sks Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 11:15AM Day: 16 Month: Mar Year: 19 89

ACTUAL PLUGGING REPORT Hole reported plugged as above.

Order 200 sks 60/40 Poz w/6% Gel and 2 sks Flocele/Celloflake.

Elevation 2632' Anhydrite depth 2255' - 91'

Remarks: Did not penetrate Arbuckle, cemented by Halliburton.
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

Signed David K. Wann
(TECHNICIAN)

David K. Wann

INVOICED
DATE 5-16-89
INV. NO. 24855