

6 100404

12-4

251

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,951-00-00

NW NW SW, SEC. 5, T 9 S, R 26 (W)E

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Minium Well # 1

Operator: Viking Resources

County Sheridan 131.37

Name & Address 120 South Market

Well Total Depth 4042 feet

Suite 518

Conductor Pipe: Size feet

Wichita, Ks. 67202

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Mallard JV Inc. License Number 4958

Address Wichita, Ks.

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Secretary

(company name) Mallard JC Inc. (phone)

were: Spot plugs through drill pipe w/heavy mud between all plugs.

1st plug at 2270' w/25 sks Rathole: 15 sks

2nd plug 1400' w/100 sks Mousehole: 10 sks

3rd plug at 310' w/40 sks

4th plug at 40' w/wiper plug and 10 sks

Plugging Proposal Received by David K. Wann (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 4:30AM Day: 4 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Hole reported plugged as above. Order 290 sks
60/40 poz w/6% gel and 2 sks celoflake or flowcele.

RECEIVED STATE CORPORATION COMMISSION

JAN 17 1990 01-17-1990

Remarks: Elevation: 2671 GL, Anhydrite depth: 2263 - 2299'. CONSERVATION DIVISION Wichita, Kansas
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 26 1990

Signed David K. Wann (TECHNICIAN)

INV. NO. 27168

FEB 09 1990