

6 070909

4-4

320

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,999-00-00

W/2 SW SW SEC. 6, T 9 S, R 26 W/EX

660 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4661

Lease Name Popp A Well # 1-6

Operator: Galloway Pet. Exp Inc.

County Sheridan 131.62

Name & Address 360 Broadway Plaza Bldg.

Well Total Depth 4050 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Casey Galloway

Surface Casing: Size 8 5/8 feet 233

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Galloway Drilling Co. Inc. License Number 5783

Address 340 Broadway Plz 105 S. Broadway Wichita, Ks. 67672

Company to plug at: Hour: _____ AM Day: 4 Month: April Year: 19 91

Plugging proposal received from Carl McGuire Galloway Drilling Inc.

(company name) Galloway Drilling Inc. (phone) _____

were: 8 5/8 - 233 ft. s.p. cwc w/170 sks 60/40 poz 25 gel 3% ca cl By Allied.

K. C. well. Elv. 2662 Anhy 2224; no circulation problems;
mud condition 44 vis - 9.3 weight. 1l water loss.

Proposal 190 sks 60/40 poz 6% gel 3% ca Cl. Spot with drill stem.

Circulate hole. Heavy mud between all plugs. No arb. 25 sks at 2235 -

100 sks w/1 sk f.c. at 1380 ft. - 40 sks at 280 ft. - 10 sks at 40 ft.

Plugging Proposal Received by Marion J. Schmidt
15 sks in rathole (circ) (TECHNICIAN) *MJS*

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:30AM Day: 4th Month: April Year: 19 91

ACTUAL PLUGGING REPORT Galloway ordered 190 sks 60/40 poz 6% gel 35 cal cl

RECEIVED

circulated hole. Spotted w/drill stem. heavy mud between all plugs.

STATE CORPORATION COMMISSION

1st plug at 2235 w/25 sks cement

APR 22 1991

2nd plug at 1380 w/100 sks cement w/1 sk f.c.

04-22-1991

3rd plug at 280 w/40 sks cement

WICHITA, KANSAS

4th plug at 40 w/10 sks cement 15 sks in rathole Circulate cement

Remarks: Allied Cement.

(If additional description is necessary, use BACK of this form.)

INVOICED

(copy) did not observe this plugging.

DATE 4-29-91

INV. NO. 31696

Signed *Marion J. Schmidt*
Marion J. Schmidt (TECHNICIAN)