

To: 6 070848
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Operator: Mid Continent Energy Corp
Name &

Address 155 N. Market #206

Wichita, Ks. 67202

Bradley R. Buehler Inc

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Lloyd Drilling Inc. License Number 3300

Address _____

Company to plug at: Hour: AM Day: 9 Month: July Year: 19 90

Plugging proposal received from Mike Deenehan

(company name) Lloyd Drilling Inc. (phone) _____

were: 8 5/8 229 ft w/150 sks common 3%. Allied Cementing Co.

Elev. 2615. Anhy 2194. No circulation problems. Mud condition 48 vis. 10 water loss.

8.9 weight. Proposal 200 sks 60/40 poz 6% gel 3 % cc. lsk fc. Spot with drill stem,

circulate heavy mud between all plugs 25 sks at 2220 ft. 100 sks at 1340 ft. 40 sks 275
10 sks at 40 15 sks rathole Cir. 10 sks mousehole Cir.

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:00 PM Day: 9 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Mid Continent ordered 200 sks 60/40 poz 6% gel 1 sk f.c. and

8 5/8 plug. Spotted cement with drill stem, heavy mud between all plugs.

1st plug 25 sks at 2220 ft. 2. plug 100 sks w/1 f.c. at 1340 ft.

3. Plug 40 sks at 275 ft. 4th plug 10 sks on wiper plug at 40 ft.

15 sks rathole cir. 10 sks in mousehole cir.

Remarks: Cemented by Allied
(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

DATE 7-24-90

INV. NO. 28720
7-9 SEP 14 1990

7-9
API NUMBER 15- 179-20,964-00-00

N/2 N/2 SE, SEC. 8, T 9 S, R 26 W/E

2310 feet from S section line

1320 feet from E section line

Lease Name Shatzell Farms Well # 1

County Sheridan 13020

Well Total Depth 4006 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 229

RECEIVED
STATE CORPORATION COMMISSION
07-13-1990
JUL 13 1990

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt