

12-6
123
R
4-060275

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,027-00-00
100'E.of
NE SW SW /4 SEC. 14, 09 S, 26 W
990 feet from S section line
1090 feet from E section line

Operator license# 9482

Lease Popp well # 1

Operator: National Petroleum Reserves

County Sheridan

135.36

Address: 250 N. Rock Road
Suite 340
Wichita, Kansas 67206

Well total depth 4165 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 297 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Emphasis Oil Operations License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 5:15P.M. Day: 6 Month: December Year: 91

Plugging proposal received from: John Collins

Company: Emphasis Oil Operations Phone: _____

Were: Order 200 sxs. 60.40 pozmix - 6% gel. with 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:15P.M., Day: 6, Month: December, Year: 91

Actual plugging report:

- 1st. plug at 2340' with 25 sxs. - Anhydrite 2321' - 2359'.
- 2nd. plug at 1380' with 100 sxs. - Dakota 1080' - 1380'.
- 3rd. plug at 350' with 40 sxs. - Surface pipe to 297'.
- 4th. plug at 40' with 10 sxs.

RECEIVED
STATE CORPORATION COMMISSION


Rathole with 15 sxs.

Mousehole with 10 sxs.

DEC 16 1991
12-16-1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Halliburton Cementing.

I did/did not [] observe the plugging.



INVOICED

DATE 1-7-92
INV. NO. 34220

J. S.

(agent)