

4-060821

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

1-7-96

API Number: 15-179-21,082-00-00
170'S.of
NE NE NE /4 SEC. 15, 09 S, 26 W
4780 feet from S section line
330 feet from E section line

Operator license# 31701

Lease: Reidel Well # 1

Operator: Lester Senesac Oil & Gas Exploration

County: Sheridan 133.84

Address: P.O. Box 305
Hill City, Kansas 67642

Well total depth 4118 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling Company, Inc. License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: 2:15 P.M. Day: 7 Month: January Year: 1996

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Company, Inc. Phone: 913-625-5183

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 4:15 P.M., Day: 7, Month: January, Year: 1996

Actual plugging report:

- 1st. Plug at 2340' w/25 sxs. - Anhydrite 2310' - 2348'.
- 2nd. Plug at 1350' w/100 sxs. - Dakota 1045' - 1345'.
- 3rd. Plug at 300' w/40 sxs. - Surface pipe to 250'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 15 sxs.
- Mousehole with 10 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO SIX Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 2620 GL

I did [] did not [X] observe the plugging.

JAN 23 1996

DATE

INV. NO. 44701

RECEIVED
STATE CORPORATION COMMISSION
Elevation: 2620 GL
JAN 19 1996
CONSERVATION DIVISION
Wichita, Kansas
AK (agent)
Form CP-2/3