

To: 6 100397
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

X 10-1
API NUMBER 15- 15-179-20,949-00-00
E/2 NW NW, SEC. 19, T. 9 STATE CORPORATION COMMISSION
4620 feet from S section 16
4290 feet from E section 12
RECEIVED
11-20-1989
CONSERVATION DIVISION
WICHITA, KANSAS

TECHNICIAN'S PLUGGING REPORT
Operator License # 6588
Operator: Woodman-Iannitti Oil Comp
Name & Address Box 308
Great Bend, Ks. 67530

Lease Name Minium Well # 1
County Sheridan 126.75
Well Total Depth 3900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Woodman Iannitti Drilling Company License Number 5122
Address Great Bend, Ks. 67530

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Rich Wheeling
(company name) Woodman Iannitti (phone) _____

were: Spot plugs through drill pipe w/heavy mud between all plugs.

1st plug at 2287' w/25 sks Rathole 15 sks

2nd plug at 1415' w/100 sks

3rd plug at 310' w/40 sks

4th plug at 40' w/wiper plug and 10 sks

Water well w/15 sks _____ Plugging Proposal Received by David K. Wann
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:00 PM Day: 1 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT _____ Order 205 sks 60/40 poz w/6% gel and

2 sks celloflake/flowcel

Hole reported plugged as above.

Remarks: Elevation 2686' GL, Anhydrite depth: 2287'
Did not penetrate Arbuckle, Cemented by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

~~XXXXXX~~ did not observe this plugging.

INVOICED

DATE 12-4-89

INV. NO. 26565

Signed David K. Wann
(TECHNICIAN)
David K. Wann