

4-060378

2-16

42
R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,062-00-00

N2 NW NE /4 SEC. 22, 09 S, 26 W
4950 feet from S section line
1980 feet from E section line

Operator license# 4661 Lease Simon well # 1-22

Operator: Galloway Petroleum Expl. County Sheridan 136.50

Address: 105 S. Braodway Well total depth 4200 feet
Suite 360 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 271 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: 11:00P.M Day: 16 Month: February Year: 93
Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone:

Were: Order 190 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 11:00P.M, Day: 16, Month: February, Year: 93

Actual plugging report:
1st. plug at 2360' w/25 sx. - Anhydrite 2345' - 2380'.
2nd. plug at 1400' w/100 sx. - Dakota 1099' - 1400'.
3rd. plug at 325' w/40 sx. - Surface pipe to 271'.
4th. plug at 40' w/10 sx.
Rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1993
02-24-1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2674 GL

I did did not X observe the plugging.

[Signature]
(agent) E.O.P.

INVOICED
DATE 3-1-93
37425
INV. NO.