

3-4  
4- 041354

20  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-21,030-00-00

82 SW SW /4 SEC. 25, 09 S, 26 W  
330 feet from S section line  
4620 feet from E section line

Operator license# 5886

Lease Transue well # 1-25

Operator: Chief Drilling, Inc.

County Sheridan

Address: 224 E. Douglas #3530  
Wichita, Kansas 67202

Well total depth 4120 feet <sup>133.90</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Chief Drilling, Inc. License# \_\_\_\_\_

Address: Wichita, Kansas 67202

Company to plug at: Hour: \_\_\_\_\_ Day: 4 Month: March Year: 92

Plugging proposal received from: Harold Dinkel

Company: Chief Drilling, Inc. Phone: \_\_\_\_\_

Were: Ordered 200 sx. 60/40 pozmix - 10% gel. with 1/4# F.C.  
Spot all plugs through drill pipe and displace with mud.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 10:00A.M., Day: 4, Month: March, Year: 92

Actual plugging report: \_\_\_\_\_

1st. plug @ 2275' w/25 sks. - Elev. 2609'.

2nd. plug @ 1330' w/100 sks. - Map. 1575'.

3rd. plug @ 300' w/40 sks. - Dakota Top - 1034'

4th. plug @ 40' w/10 sks. - Dakota Bottom - 1334'.

Anhy. 2258' - 2320'.

15 sks. in Rathole.

10 sks. in Mousehole.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES  NO

Plugged through TUBING , CASING . Elevation: 2609 GL

I did  did not  observe the plugging.

Dennis L. Hamel

DATE 3-17-92

(agent)

INV. NO. 34764

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
03-13-1992  
MAR 13 1992

CONSERVATION DIVISION  
Wichita Kan