

6 070539

FEB 1 1987 02-01-1987

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179-20, 885-00-00

NW-SE-SW, SEC. 27, T. 9 S, R. 26 W

990 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name L.K. Siman Well # 1

Operator: Rains + Williamson Oil Co. County Sheridan 134.39

Name & Address 435 Page Court, 220<sup>th</sup> Douglas, Well Total Depth 4135 feet

Wichita, Kansas 67202 Conductor Pipe: Size 0 feet

Juanita Green Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated Tag # 62

Plugging Contractor Rains + Williamson Oil Co License Number 5146

Address 435 Page Court, 220 West Douglas, Wichita, Kansas 67202

Company to plug at: Hour: 8:15 AM Day: 1st Month: Feb Year: 1987

Plugging proposal received from Mike Adfrey

(company name) Rains and Williamson Oil Co Inc (phone) 316-265-9684

were: 8 5/8" - 301' SP. CUC<sup>u</sup>/190<sup>SK 60</sup> 1/40 Pozmix 6% Gel - 3% Ca. Cl. - By B.J. Titan

Proposal 190<sup>SK 60</sup> 1/40 Pozmix 6% Gel - Ca. Cl. 1<sup>SK</sup> CUC + 8 5/8" Plug

no Circulation Problems, L.K.C. Well, Ely. 2632, Sub 2279

Mud Condition 44-Viscosity, 9.4<sup>u</sup> Weight, 10.4 Water loss. With Drill

Stem Sprt, 25<sup>SK</sup> cmt @ 2310', 100<sup>SK u</sup> 1/2 Cello @ 1050', 40<sup>SK</sup> cmt @ 350', 10<sup>SK</sup> cmt @ 40<sup>u</sup>

15<sup>SK</sup> In Rat Hole (Cuc) Plugging Proposal Received by Marion Schmidt

Heavy Mud between all plugs. (TECHNICIAN)

Plugging Operations attended by Agent? All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:15 PM Day: 1st Month: Feb Year: 1987

ACTUAL PLUGGING REPORT Ordered 190<sup>SK 60</sup> 1/40 Pozmix 6% Gel - 3% Ca. Cl.

1<sup>SK</sup> Cello Slake, spotted with Drill Stem, with heavy mud

between all plugs.

1st Plug @ 2310<sup>u</sup> 25<sup>SK</sup> cmt, 2ND Plug @ 1050<sup>u</sup> 100<sup>SK</sup> cmt 1/2 Cello

3RD Plug @ 350<sup>u</sup> 40<sup>SK</sup> cmt, 4<sup>th</sup> Plug 10<sup>SK</sup> cmt @ 40<sup>u</sup>

15<sup>SK</sup> Cmt In Rat Hole (circulate) Cemented by B.J. Titan.

2-2-87 Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-10-87

INV. NO. 16108

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Signed

Marion Schmidt (TECHNICIAN) P