

9-21-87

6 070598

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,907-00-00  
SENE NE SEC. 27, T 9 S, R 26 W/4E  
4290 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
5146  
Operator License #  
Operator: Rains and Williamson Oil Co.  
Name & Address: 220 West Douglas #435  
Wichita, Kansas 67202  
Juanita Green

Lease Name George Simon Well # 1  
County Sheridan 125.20  
Well Total Depth 4160 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_ Rig Tag #62

Plugging Contractor Rains and Williamson License Number 5146  
Address 220 West Douglas #435 Wichita, Ks. 67202

Company to plug at: Hour: 7:00 PM Day: 21 Month: Sept Year: 19 87

Plugging proposal received from Larry Henderleiter  
(company name) Rains and Williamson (phone) 316-265-9686

were: 8 5/8" 331 SP CWC 2/220sks 60/40 Pozmix 2 - 3 By B. J. Titan  
Elevation 2649' Anh 2291' No Arbuckle. No circulation problems, mud 48 Vis,  
9.6 weight, 11.8 water loss. Proposal 200 sks 60/40 Pozmix 6% Gel 3% Ca Cl  
1 Celloflake and plug. Spot with drill stem, recondition hole, heavy mud between  
all plugs. 25 sks at 2310'; 100 sks w/1 Celloflake at 1375'; 50 sks at 380'  
10 sks at 40'; 15 sks rat hole. (circulate)  
Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 7:00 PM Day: 21 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Ordered 200 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 1 sks Celloflake  
and 8 5/8" plug. Spot with drill stem, heavy mud between plugs.

1st plug at 2310' w/25 sks cement; 2nd plug at 1375' w/100 sks cement w/1 sks Celloflake;  
3rd plug at 380' w/50 sks cement; 4th plug Hulls and plug at 40' w/10 sks cement.  
15 sks in rat hole (circulate) Cemented by B. J. Titan.

Remarks: \_\_\_\_\_  
(if additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
10-09-1987  
OCT 9 1987

INVOICED  
9-25-87  
(if not) observe this plugging.

Signed Marion J. Schmidt  
(TECHNICIAN)

DATE 10-12-87  
INV. NO. 18475