

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20218-00-00

158141915
02-14-1975
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tilco, Inc.

Complete Address 400 Century Plaza, Wichita, Kansas 67202

Lease Name Lindquist Well No. 2

Location NW SW SW Sec. 35 Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3575"

Abandoned Oil Well Gas Well Input Well XXX SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:30 A Day 12 Month 2 Year 1975

The above well was plugged as follows:

Total Depth 3575' 8 5/8 csg set at 204' cwc 150 sk.

5 1/2 csg set at 3573' cw 150 sx cem.

Top of tbg. fish (2700') Pushed 5 1/2 wood plug to 2700' -dumped 4 sx cem W/dump bailer.

5 1/2 csg squeezed thru "Dakato Section" top of cem. 150'. No pipe recovered.

Perf. 5 1/2 csg at 320'.

Mixed & pumped down 5 1/2 csg with 10 sk gel & water -released plug & pumped 100 sk

50-50 poz cem. 6% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo P. Massey
Well Plugging Supervisor

INVOICED

DATE 2/14/75
INV. NO. 833-W