

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-00389-00-01

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 3 1969  
CONSERVATION DIVISION  
Wichita, Kansas

2-3-69

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name O. A. Sutton

Complete Address: 800 Sutton Place Wichita, Kansas

Lease Name Gelina Well No. 1

Location SE SE SW Sec. 21 Twp. 9 Rge. 19 (X) (W) XX

County Rooks Total Depth 3693

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated: (OWWO)

Plugging Contractor: Gabbert-Jones

Address: Wichita, Ks. License No.     

Operation Completed: Hour 5:30P Day 1 Month 2 Year 1969

The Above well was plugged as follows:

RTD 3693' 8 5/8 setaat 215' CWC Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk cmt thru drill pipe. Heavy mud to 210' set ceme ting plug and displaced 20 sk cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cement to base of cellar. Plugged rat hole with 2 sk cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Pro J. Massey  
Well Plugging Supervisor

DATE 2/3/69  
INV. NO. 9275-W