



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20114-00-00

Dear Sir:

Mr. Cain of Peel Bros. Inc. has this date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney, Inc.

Complete Address: 925 Sutton Place Wichita, Ks.

Lease Name: Keas Well No. 1

Location: C NW NE Sec. 17 Twp. 9 Rge. 17 (E)(W) X

County: Rooks Total Depth 3516 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cain was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 650' and displace
70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with
2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1968

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

07-01-1968

Leo F. Massey
Conservation Division Agent