

15-163-19228-02-00

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 144-51 County: Rooks

Location: SW NW SE Sec. 5 Twp. 9 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3461

I have this date completed supervision of plugging of:

Lease Name: Fike Well No. A3

Operator's Full Name: Murfin Dpg Co

Complete Address: 617 Union Center Wichita, Kans

Plugging Contractor: Ace Pipe Pulling Co & Sun Cementing Co

Address: Great Bend, Kans License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 22 Month 11 Year 58

The above well was plugged as follows:

8 5/8" at 162' circulated with cement - 5 1/2" 3450' with 75 sax cement behind - P.B. to 3415', perforated ~~3415'~~ 3323'.

Dakota broke in - shot tubing off at 2806' - pulled 2230' 5 1/2" to 600', circulated hole with heavy mud (Gel) through 5 1/2" - spotted 20 sax cement through 5 1/2" at 600', heavy mud to 150', spotted 20 sax cement through 5 1/2" at 150', heavy mud to 35', set bridge and 10 sax cement to 0'.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC S T 9 R 17w
BOOK PAGE 144 LINE 31

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 - 1958
CONSERVATION DIVISION
Wichita, Kansas
12/2/58