

15-163-00717-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

39-30
FILE NO. ~~XX5005X~~
LOCATION NE NE SW
SEC. 6 TWP. 9 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Moos

Operator Morganstern-Specter Address Russell, Kans

Field _____ County Rooks

Total Depth 3391 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe briefly the manner in which the well was plugged)

10 3/4" at 152' circulated with cement - 5 1/2" at 3389' with 100
sax cement behind, perforated at 3298'.

Filled with sand to 3290', set 4 sax cement with dump bailer,
pulled 2612' 5 1/2" - filled hole with heavy mud to 150', set rock
and 20 sax cement, heavy mud to 35', set rock and 10 sax cement
to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

District Conservation Agent's

Date 3-6-56

3/6/56

PLUGGING
FILE SEC 6 T 9 R 17W
BOOK PAGE 39 LINE 30